

NGRI TECHNICAL REPORT No: 82—193

# **GEOPHYSICAL INVESTIGATIONS FOR DUL-HASTI TUNNEL, KISHTWAR, J&K STATE**

( SPONSOR : NHPC, NEW DELHI )

A PROJECT EXECUTED BY ENGINEERING GEOPHYSICS GROUP



**NATIONAL GEOPHYSICAL RESEARCH INSTITUTE  
HYDERABAD - 500 007.**

JANUARY - 1982

This project was mainly funded by N.H.P.C., New Delhi. Fullfilling the terms of the contract, Resistivity and Seismic Surveys along the tunnel alignment were done. Besides these, Seismic and Resistivity work in the Shalimar Nala was also carried out at the oral request of N.H.P.C. while the team was working at Kishtwar. N.G.R.I. as a part of its R & D activity carried out telluric survey along the alignment. The result of the main work (funded by N.H.P.C.) and supplementary work (funded by N.G.R.I.) is reported in the following pages. The following were associated with the job.

Area Chairman	:	S. BALAKRISHNA
Project Leader	:	G. VARADARAJAN
Participants		
Seismic & Resistivity Investigations	:	K. SUBRAHMANYAM T. SESHUNARAYANA D. JANAKIRAMARAJU Y. RAMAMOCHANRAO
Telluric Survey	:	S.V.S. SARMA T. HARINARAYANA
Geological aspects	:	M.N. RAO

:: ii ::

C O N T E N T S

1.	Introduction	.....	1
2.	Location and Phygeography	.....	2
3.	Geology	.....	3
4.	Geophysical Investigations	.....	6
5.	Field observations	.....	11
6.	Discussions	.....	14
7.	Recommendation	.....	17
8.	Annexure -1	.....	18
	Telluric Investigations		
9.	Acknowledgements	.....	23
10.	Enclosures (Maps -9 nos.)	.....	Flap inside cover.